AFE- DRILLING COST ESTIMATE - OGINI-A 4 MH & HZ Well (Durga 14)

Project :	**OML-26**	**Surface Hole**	**914 m, MD**	**0.00**	**12-1/4 inch Drilling and 9-5/8 in. Csg. to 914m**
Well :	**OGINI-A 4 MH & HZ**	**Intermediate Hole-PH**	**2,277 m, MD**	**0.00**	**8-1/2 inch PH Drilling and Plug Back. 2277 m**
Type :	**GAS DEVELOPMENT WELL**	**Intermediate Hole- MH**	**2,443 m, MD**	**21.00**	**8-1/2 inch MH Drilling and 7 in. Csg. to 2443 m**
		Production Hole	**2,913 m, MD**	**13.00**	**6 inch HZ Drilling to 2913 m**
		Planned Days		**34.00**	**OBJECTIVE: Drill as a horizontal well with the drain hole within the E-2100 reservoir**

ITEM	DESCRIPTION	Daily cost, $	Fixed cost, $	Total cost, $	Remarks
1.0	**RIG COSTS**				
1.1	Day Rate	5,000	-	170,000	**BOGEL**
	TOTAL RIG			**170,000**	
2.0	**Fuel**	-	-	-	**100% Gas**
3.0	**FORMATION EVALUATION**				
3.1	Electric Logging Services	-	-	-	
3.2	Mud Logging Equip. & Services/Personnel/Rentals	500		17,000	**Geomud**
	TOTAL FORMATION EVALUATION			**17,000**	
4.0	**WELL SERVICES**				
4.01	D&C Fluids / Mud Chemicals	-		151,134	**(OH*0.40*$180) OBM For 8-1/2'' & 6'' inch '')**
4.02	D&C Fluids / Mud Service / Personnel/ Rentals	300	-	10,200	**Geomud**
4.03	Cement Materials / Additives	-		21,492	**CBNL Cementing Additives**
4.04	Drill Bits / Nozzels	-	16,300	16,300	**1:- 8-1/2'' PDC Bit , 1:- 6" PDC Bit**
4.05	Solids Control Equipment - Centifuges	200	2,250	6,800	**SSENL /(Screens BOGEL)**
4.06	Solids Control Equipment - Verti - G	200	2,250	6,800	**SSENL /(Screens BOGEL)**
4.07	Environmental Rental services/Waste Management	150		5,100	**SSENL**
4.11	Cementing Services/Rental Accessories		-	8,000	**CBNL Cementing service**
4.12	Casing/Tubing / Screen Running services	-	-	1,200	**BOGEL**
4.13	Drilling & Fishing tools	-	4,000	4,000	**ALNL JAR SERVICES**
4.14	Wellhead Services			7,500	**WELLHEAD SERVICES - Cameron**
4.15	SLB RSS			782,280	**SLB RSS Drilling for 8-1/2'' MH & 6''HZ & INSURANCE COST PER DAY**
	TOTAL WELL SERVICES			**1,020,806**	
6.0	**SUPERVISION**				
6.1	Supervision on the Rig	1,200		40,800	**SEEPCO**
6.2	Supervision office and consultancy	800		27,200	**SEEPCO**
	TOTAL SUPERVISION			**68,000**	
	SERVICES TOTAL COST, USD	**8,350**		**$ 1,275,806**	
	TANGIBLES TOTAL COST, USD			**$ 246,877**	**SEEPCO Tangibles & Cameron-Wellheads**
	DRILLING TOTAL COST, USD			**$ 1,522,683**	

neline Summary	Depth ft MD BRT	Iteration Dist, Hrs	No. Of Days
8-1/2" Main Hole Drilling	2443	389.30	16.10
7" Casing & Cementation; WH & BOP operations	2443	119.40	4.90
6"Drain Hole Drilling	2913	312.40	13.00
	Total Days		34.00

TOTAL COST (PH /MH& HZ) :- $2,281,324